



Tower Site Preparation Instructions

9' Tower

Dimensional Specifications

- **Height:** 9'
- **Width:** 10-3/4"
- **Depth:** 6"
- **Thickness of Steel:** 11 Gauge
- **Weight:** 167 lbs.

Tower Mounting Hardware Kits*

- Part # 7476 for new concrete
- Part # 7477 for existing concrete

**If you did not purchase mounting hardware and would like to, please call 800-451-1460.*

Site Preparations

1. Concrete mounting pad should be at least 16" in depth and 2' in diameter.
2. Insert the 3/4" x 12" galvanized rods per mounting template provided.
3. A minimum 2" of thread must be exposed above level of concrete.
4. If a wired tower, position conduit that will contain the electrical and phone wiring into center of the concrete pad per the mounting template.
 - a. When running the wire, provide at least 48" of wiring above the concrete pad.
5. Let concrete set for a minimum of 48 hours to cure.